



Jamaica Public Service Company Limited

REQUEST FOR PROPOSAL

OWNERS ENGINEER SERVICES

ROCKFORT DIESEL STATION

UNIT #2

MAJOR OVERHAUL 2022

RFP # 883111

MAY 2021

Contents

1. Background	3
2. Scope of Works	3
2.1 Pre-Overhaul Planning	3
2.2 Overhaul Support	4
3. Submission of Time Sheets	5
4. Schedule	5
5. JPS Labor Assistance	5
6. Accommodation and Transportation in Jamaica	5
7. JPS Measuring Instruments and Tools	5
8. HSE (Health Safety and Environment) Policy	5
9. Insurance	6
10. Division of Responsibility	6
11. Deliverables and Schedules	6
12. General Instructions to Bidders	6
12.1 Points of Contact (POC)	6
12.2 Communication Regarding the RFP	7
12.3 RFP Amendment and Cancellation	7
12.4 Confidentiality of Data	8
12.5 Written Clarification	8
12.6 Oral Clarification	8
12.7 RFP Responses Submission	8
13. RFP Response Format	9
13.1 RFP Response Prices	9
13.2 Technical Response	9
13.3 Proposed Withdrawal	9
13.4 Cost of Proposal Preparation	9
13.5 Proposal Rejection	10
14. Evaluation Criteria	10
14.1 Award Criteria	10
14.2 RFP Response Currency	11
14.3 Award of Contract	11
14.3.1 Award or Rejection	11
14.4 Notification of Award	11
15. Appendix	12
15.1 Location of the Rockfort Diesel Station	12
15.2 Unit Information	13
15.3 Proposal Costs	14
15.3.1 Time and materials Rates (Option 1)	15
15.3.2 Full Time Marine Engineer (Option 2)	15
Note: Contractors must submit proposals for option no. 1 and option no. 2 for consideration.	15
15.4 Schedule Requirements	15

1. Background

Jamaica Public Service Company Limited (JPS) is an integrated electric utility company engaged in the generation, transmission and distribution of electricity throughout the island of Jamaica. JPS owns and operates 28 generating units and also purchases power from seven independent power producers (IPP). JPS assets include conventional thermal plants (374 MW), hydro and wind (29.12 MW), 50 substations, approximately 1200 km of transmission lines and 20,534 km of distribution lines.

The common shares of JPS are held 40% by Marubeni Corporation through its subsidiary Marubeni Caribbean Power Holdings (“MCPH”); 40% by Korea East West Power Company (“KEWP”); 19.9% by the Government of Jamaica (“GOJ”) and the remaining 0.1% by a group of minority shareholders.

The Office of Utilities Regulation (“OUR”) is the independent regulatory agency with responsibility for regulating the electricity sector in Jamaica.

JPS has the following status with Jamaica Customs – Authorized Economic Operator (AEO). It is an internationally recognized quality mark which indicates that the JPS supply chain is secure, and that the JPS customs’ procedures and policies are compliant. With this designation, JPS Warehouse and Procurement Teams are subject to audit and monitoring by Jamaica Customs.

The Rockfort Diesel Station Unit #2 is scheduled to undergo its biennial major maintenance in January 2022 for a period of 35 calendar days. During this period a series of inspection and maintenance activities will be performed. The objectives of the overhaul are to improve the efficiency and reliability of the unit without any safety incidents.

The company is requesting proposals from specialist contractors to provide Owners Engineering Services for the Rockfort Diesel Station Unit #1 Major Overhaul on a **Time and Materials basis** as outlined in this RFP document.

2. Scope of Works

The works involved in Owners Engineer Services shall include but not limited to the following:

2.1 Pre-Overhaul Planning

Consultant must review and provide recommendations on the planned Overhaul work scope, with an emphasis on the following aspects:

a. Pre-outage Assessment of Unit

Review of pre-outage Unit measurements, reading, and equipment health indicators to anticipate repairs to be undertaken or needed during the Overhaul.

b. Outage Scope Review

Review of historical overhaul findings, lessons learned, recommend overhaul work scope delineation , quality assurance/quality control measures to address such historical issues and prevent recurrence

c. Outage Schedule Consultations

Based upon known equipment condition and historical outage findings, opine on the best approach to provide flexibility in the Overhaul schedule for emergent repairs and associated delays.

d. Review Performance Indicators, Equipment and System Health

Review Rockfort Station Unit RF1, Unit RF2, and balance of plant equipment and system health and performance indicators. Interface with Rockfort operations team to identify priority operational improvements that can be implemented during the Overhaul or some time following the Overhaul. The focus of the evaluation must include the lubricating oil systems and the cooling water intake systems or any other areas of concern identified by the Rockfort operations team.

e. Root Cause Failure Investigations

Participate in Root cause investigation related to high liner wall temperatures on the unit.

f. Pre-Outage Planning Meetings

Attend and participate in virtual or onsite pre-outage planning meetings as requested by the Owner.

2.2 Overhaul Support

During the Overhaul, Consultant shall support the Rockfort maintenance and operations teams by executing the following tasks:

a. Inspection and Assessment of Engine Components

During the Overhaul the consultant will conduct a site visits at the Rockfort Station to the following

- Inspect the as-found condition of the opened and measured main bearings
- Observe the inspections of the pistons and cylinder lining wear patters.

The intent of this visits is to assess any abnormal conditions related to the priority components and consult with the Rockfort maintenance and operations teams regarding repairs or replacements proposed by the Overhaul contractor.

b. Verification of Critical Measurements

The consultant will be required in assisting in the review and validating of critical measurement checks conducted during the overhaul.

c. Reporting

Review, interpret and provide recommendations on the following

- Daily outage work reports
- Preliminary and final measurement record reports
- Post-outage performance test results prepared by the contractor(s) executing the Overhaul work scope.

NB. Contractor reports will be reviewed on a daily basis by Consultant with the Rockfort maintenance and operations teams.

Upon completion of the overhaul, Consultant must review the final overhaul report to verify that it appropriately characterizes the events of the overhaul and that the as-left tolerances and start-up test results are consistent with those documented during the overhaul.

The consultant must provide a final report of their services

3. Submission of Time Sheets

The consultant will charge the works done on a time and materials basis.

The consultant will be required to submit weekly time sheets to the designated JPS representative for approval.

4. Schedule

The consultant is required to complete all works by February 2022.

5. JPS Labor Assistance

JPS will provide local plant engineers to assist the consultant in executing their services.

6. Accommodation and Transportation in Jamaica

JPS will provide hotel accommodation and Transportation for the Consultant crew members.

7. JPS Measuring Instruments and Tools

JPS will provide measuring instruments or tools the consultant may require to do works.

8. HSE (Health Safety and Environment) Policy

The consultant will be expected to abide by JPS HSE Policy and Procedures

Consultant must conform to all GOJ (Government of Jamaica) COVID-19 Protocols.

9. Insurance

The contractor must provide comprehensive insurance to protect their property and workers.

10. Division of Responsibility

Resource / Service	Contractor	JPS
Supply of Utilities (Compressed Air , Electricity , Water)		X
Tools and instruments / certificates must be included		X
Office Facilities for Specialist Contractors		X
Workshops , access to Workshop Equipment and workshop tools		X
Safety Equipment	X	
Custom Clearance		X
Local Transportation of Equipment		X
Hotel Accommodation for Consultant Workers		X
Local Transportation of Consultant Workers		X
Participate in update meetings (measurement, inspection and findings)	X	X
Participate in daily debrief meetings (Option 2 – Section 15.3.2)	X	X

11. Deliverables and Schedules

ITEMS	TASKS AND DELIVERABLES	DATES	RESPONSIBILITY
1	RFP invitations to selected contractors	May 31, 2021	JPS
2	Question submitted by Bidder	June 4, 2021	Consultant
3	Response to question	June 9, 2021	JPS
4	Bidder provide their intention to bid	June 11, 2021	Consultant
5	Completion of RFP and deadline for submission of bids to JPS	11:59PM June 17, 2021	Consultant
6	Bid Opening	June 18, 2021	JPS

12. General Instructions to Bidders

12.1 Points of Contact (POC)

All communications and questions with JPS regarding the RFP must be directed to the following points of contact (POC).

Name: **Mr. Kolonje McKenzie**
 CC: Mrs. Ann-Marie Woodham, Ms. Melisa Richmond
 Address: Jamaica Public Service Company Ltd

113 Washington Boulevard
Kingston 20, Jamaica WI

Email: kompckenzie@jpsco.com cc: aaiken@jpsco.com mcrichmond@jpsco.com

12.2 Communication Regarding the RFP

- a. Unauthorized communications concerning this RFP with other company employees, executives or contractors may result in immediate disqualification.
- b. All communication and questions should be submitted in writing, electronically to the POC. In order to ensure consistency in the information provided to the RFP Contractors, responses to questions received will be communicated to all participants without revealing the source of the inquiries.
- c. Only written responses will be considered official and binding. JPS reserves the right, at its sole discretion, to determine appropriate and adequate responses to questions and request for clarification.
- d. Bidders contact information shall be provided for RFP and thereafter contained within all correspondence containing questions and clarifications arising.

Requirements include:

- i. Company's name, company address and phone number, contact person, email address, position
- ii. References to specific points within the RFP using section number as reference
- iii. Clear and concise questions.

12.3 RFP Amendment and Cancellation

At any time prior to the deadline for submission of bids, the Purchaser may, for any reason, whether at its own initiative or in response to a clarification requested by a prospective bidder, modify the Bidding Documents by amendment.

The amendment will be done in writing to all prospective Bidders who have received the Bidding Documents, and will be binding on them.

In order to afford prospective Bidders reasonable time in which to take the amendment into account in preparing their bids, the Purchaser may, at its discretion, extend the deadline for the submission of bids.

JPS reserves the unilateral right to cancel or reissue the RFP at its sole discretion. Bidders will respond to the final written RFP and any exhibits, attachments and amendments.

12.4 Confidentiality of Data

The Bidder should recognize that JPS operates in a sensitive business environment and, for that reason the Bidder must treat the materials and data provided by JPS as confidential. The successful Bidder may be required to agree to and execute the confidentiality agreement.

12.5 Written Clarification

JPS reserves the right, at its sole discretion, to request clarifications of any Proposal or to conduct discussions for the purpose of clarification with any or all contractors. The purpose of any such discussions will be to ensure full understanding of the proposal. Discussions will be limited to specific sections of the proposal identified by JPS and, if held, will be after initial evaluation of the Proposal.

If clarifications are made as a result of such discussion, the contractor will submit such clarifications electronically.

Refusal to respond to JPS request for clarifications may be considered non-responsive and be used as grounds for rejection of the Proposal.

12.6 Oral Clarification

If requested, the vendor will make an oral presentation to the Proposal Evaluation Team and other designated Company representatives. All expenses for the presentation will be borne by the vendor.

Late RFP Response

Any RFP Response received by the Company after the deadline for submission of RFP Responses prescribed by the Company will be rejected and/or returned unopened to the RFP Response Contractors.

12.7 RFP Responses Submission

Only Electronic submissions will be accepted, using ShareFile by Citrix. All uploads will be confidential. Additional information on this software can be accessed by clicking the links below:

- Basic Client Guide <https://citrix.sharefile.com/share/view/s1bff52f8d434781a>
- Training (video) <https://www.sharefile.com/support/training>

RFP Activities are guided by the dates stated in the Calendar of Events highlighted in Section 11 of this RFP. Observing these dates,

- 1) A combined response to questions will be shared at the time specified in the RFP.

- 2) Respondents must confirm their intention to bid in order to be setup in JPS ShareFile folder
- 3) Access to individual vendor folders will be given 1 weeks before the bid closes to eliminate any issues for bid upload by RFP deadline.
- 4) Files must be accurately labelled/named. Commercial Information must be a separate file from your Technical Overview.
- 5) ShareFile Access will be removed when the bid closes.

13. RFP Response Format

13.1 RFP Response Prices

Agreed prices for the selected Bidder shall be fixed in the contract up to end of calendar year 2022.

13.2 Technical Response

TECHNICAL PROPOSALS must include the following:

- A list of similar projects completed in the last five years
- Company Brochure
- Other information in the contractor's view that is fit for consideration

13.3 Proposed Withdrawal

The Bidders may modify or withdraw its proposal after submission, provided that written notice of the modification or withdrawal is received by the Purchaser/JPS prior to the deadline prescribed for submission of proposals.

To withdraw a proposal, the Bidders must submit a written request electronically or signed document by an authorized representative before the deadline for submitting proposals. After withdrawing a previously submitted proposal, the Bidders may submit another proposal at any time up to the deadline for submitting proposals.

13.4 Cost of Proposal Preparation

The Bidders shall bear all costs associated with the preparation and submission of its RFP Response. JPS will in no case be responsible or liable for those costs, regardless of the conduct or outcome of the RFP Response process.

13.5 Proposal Rejection

Bidders must comply with all of the terms of this RFP. JPS may reject any proposal as being non-responsive that does not comply with the terms, conditions and characteristics of this RFP or the key criteria for selection.

JPS reserves the right, at its sole discretion, to reject any and all proposals or to cancel this RFP in its entirety, and to accept a proposal other than the lowest price or proposal presented outside of this RFP that meets the company's requirement.

JPS assumes no responsibility for delays caused by any mail/bearer delivery service.

14. Evaluation Criteria

The evaluation of Proposal will be carried out for each technical proposal, taking into account (a) the contractor's relevant experience for the assignment, (b) the quality of the methodology proposed (c) the qualifications of the key staff proposed. (d) technical capability, cost of service and ability to meet target dates deadlines.

14.1 Award Criteria

JPS will evaluate proposals using an internal scoring method that weighs various parameters to give the evaluation team insight into the strengths of each proposal relative to JPS needs. JPS internal scoring method values the following proposal attributes (Order of presentation here does not reflect priority).

TECHNICAL EVALUATION

CRITERIA	Score
Technical capability	Pass/Fail
Experience with JPS model (RLB) engine or similar	Pass/Fail
Qualifications of Key Personnel	Pass/Fail
Safety Record	Pass/Fail

COMMERCIAL EVALUATION

CRITERIA	Score (%)
Price	90
Terms of payment	10
Total	100

14.2 RFP Response Currency

Prices should be quoted in USD.

14.3 Award of Contract

14.3.1 Award or Rejection

The Purchaser/JPS will award the contract to the successful Contractor whose RFP Response has been determined to be substantially responsive. The Purchaser/JPS reserves the right not to accept the lowest RFP Response if it does not meet JPS requirement.

Issuance of this RFP Response does not constitute a commitment by JPS to award any contract or purchase services offered.

The Purchaser/JPS reserves the right to accept or reject any RFP Response, and to annul the RFP Responding process and reject all RFP Responses at any time prior to award of Contract, without thereby incurring any liability to the affected RFP Response Contractors or any obligation to inform the affected RFP Response Contractors of the grounds for the Purchaser/JPS's action.

14.4 Notification of Award

Prior to the expiration of the period of RFP Response validity, the Purchaser/JPS will notify the successful RFP Response Contractor in writing by email or fax, that its RFP Response has been accepted. All unsuccessful RFP Response contractors will be notified.

15. Appendix

15.1 Location of the Rockfort Diesel Station



15.2 Unit Information

<i>Plant Location</i>	Eastern side of Kingston Harbour
<i>Commission Date</i>	December 1985
<i>Technology</i>	Two (2) Slow Speed Diesel Engine Driven Generators
<i>Installed Capacity</i>	40 MW
<i>Current MCR</i>	40 MW
<i>Operating Regime</i>	Base Load
<i>Manufacturer</i>	Mitsubishi Heavy Industries / Sulzer
<i>Type & Model</i>	Sulzer – 8RLB90F
<i>Number of Cylinders. & RPM</i>	8 / 100
<i>Horsepower</i>	28,160
<i>Cylinder Bore</i>	900 mm
<i>Piston Stroke</i>	1900 mm
<i>GENERATOR DATA</i>	
<i>Manufacturer</i>	Meidensha Electric Mfg. Co. Ltd.
<i>Type</i>	Synchronous
<i>Rated Output</i>	20,000kW ; 13,800V
<i>Frequency</i>	50 Hz
<i>Generator Rated Current</i>	1,046 A
<i>No. of Poles</i>	60

15.3 Proposal Costs

Owners Engineer Services
2.1 Pre-Overhaul Planning
a. Pre-outage Assessment of Unit
b. Outage Scope Review
c. Outage Schedule Consultations
d. Review Performance Indicators, Equipment and System Health
e. Root Cause Failure Investigations
f. Pre-Outage Planning Meetings
2.2 Overhaul Support
a. Inspection and Assessment of Engine Components
b. Verification of Critical Measurements
d. Reporting

15.3.1 Time and materials Rates (Option 1)

Provide Time and Materials rates of Consultant/s and Reimbursable expenses.

JPS will call upon the consultant on an as needed basis for works stated in section 2 prior to the outage period, during the outage and upon completion of the outage.

15.3.2 Full Time Marine Engineer (Option 2)

Submit Costing to provide a consultant/s on-site during the reassemble and commissioning phases to perform the works highlighted in section in section 2.

This duration is anticipated to be around 15 calendar days.

An experienced marine engineer is preferred for this role.

Note: Contractors must submit proposals for option no. 1 and option no. 2 for consideration.

15.4 Schedule Requirements

ROCKFORT No.2 MAJOR OVERHAUL_JAN. 2022	24.71 days	Fri 1/7/22	Mon 1/31/22
RF 2 BOP MAINTENANCE. ACTIVITIES	19.83 days	Fri 1/7/22	Wed 1/26/22
MECHANICAL MAINTENANCE DEPT. MAINTENANCE	19.83 days	Fri 1/7/22	Wed 1/26/22
PERMITS ACQUISITION & CANCELLATION	19.83 days	Fri 1/7/22	Wed 1/26/22
Acquire LOTO (MMD) on Main engine systems	1 hr	Fri 1/7/22	Fri 1/7/22
Cancel LOTO on Mechanical systems	1 hr	Wed 1/26/22	Wed 1/26/22
RF No.2 MAIN ENGINE SYSTEMS	19.75 days	Fri 1/7/22	Wed 1/26/22
TURBOCHARGERS OVERHAUL - H. REID	19.46 days	Fri 1/7/22	Wed 1/26/22
CYLINDERS 1- 8; OVERHAUL (INCLUDE PISTONS AND CYLINDER LINERS)	18.92 days	Fri 1/7/22	Tue 1/25/22
No.2 M.E. ACCESS DOORS OPENING	0.5 days	Fri 1/7/22	Fri 1/7/22
Remove Bolts and open all M.E Lantern doors	2 hrs	Fri 1/7/22	Fri 1/7/22
Remove bolts and open all M.E crankcase doors	4 hrs	Fri 1/7/22	Fri 1/7/22
Remove bolts and open liners plug space doors	1 hr	Fri 1/7/22	Fri 1/7/22
Remove bolts and open all M.E lower and upper scavenge space doors	2 hrs	Fri 1/7/22	Fri 1/7/22
Remove bolts and open manifold doors	2 hrs	Fri 1/7/22	Fri 1/7/22
Remove bolts and open M.E economizer doors	4 hrs	Fri 1/7/22	Fri 1/7/22

Remove bolts and open all M.E PUP doors	4 hrs	Fri 1/7/22	Fri 1/7/22
DISASSEMBLY OF PISTON,LINERS AND OTHER	2.33 days	Fri 1/7/22	Sun 1/9/22
Inspect all piston and liners for leaks after shutdown	1 hr	Fri 1/7/22	Fri 1/7/22
Remove M.E. 1-8 cylinder cover accessories	4 hrs	Fri 1/7/22	Fri 1/7/22
Loosen nuts and remove M.E. 1-8 cylinder covers (Nuts to be loosened prior to the start of Crankshaft deflection)	4 hrs	Fri 1/7/22	Fri 1/7/22
Loosen and remove M.E. 1-8 cylinder piston nuts (Nuts to be loosened prior to the start of Crankshaft deflection)	3 hrs	Fri 1/7/22	Fri 1/7/22
Remove M.E 1-8 Cylinder pistons	6 hrs	Fri 1/7/22	Fri 1/7/22
Remove M.E 1-8 cylinder piston rod stuffing boxes	4 hrs	Sat 1/8/22	Sat 1/8/22
Remove Cylinder Studs (33) (Check if this is necessary)	1 min	Sat 1/8/22	Sat 1/8/22
Remove M.E 1-8 cylinder, lubricating Quills	8 hrs	Fri 1/7/22	Fri 1/7/22
Remove M.E cylinder liners (as required)	12 hrs	Sat 1/8/22	Sun 1/9/22
Remove M.E 1-8 cylinder jacket ring (insert)	8 hrs	Sat 1/8/22	Sat 1/8/22
Remove M.E stand pipes	4 hrs	Sat 1/8/22	Sat 1/8/22
Remove M.E 1-8 cylinder piston cooling gland boxes	4 hrs	Sat 1/8/22	Sat 1/8/22
INSPECTION & SERVICING OF ENGINE PARTS	14.33 days	Fri 1/7/22	Fri 1/21/22
Clean and conduct DYE penetrant testing on M.E 1-8 cylinder blocks for cranks and repairs	8 hrs	Wed 1/12/22	Thu 1/13/22
Clean and conduct DYE penetrant testing on # 1 M.E 1-8 exhaust ports	8 hrs	Thu 1/13/22	Fri 1/14/22
Conduct DYE penetrant testing on #1 M.E 1-8 cylinder covers	24 hrs	Fri 1/14/22	Sat 1/15/22
M.E.1 - 8 Cylinder liners; overhaul (new liners were replaced)	48 hrs	Tue 1/11/22	Sat 1/15/22
M.E 1 - 8 Cylinder covers; overhaul	24 hrs	Fri 1/14/22	Sat 1/15/22
M.E.1 - 8, Cylinder pistons(Crown, Rod, Skirt, Ring); Overhaul	96 hrs	Fri 1/14/22	Fri 1/21/22
M.E.1 - 8, Cylinder stand pipes; Overhaul	24 hrs	Fri 1/7/22	Sun 1/9/22
M.E.1 - 8, Cylinder, lubricating quills; Overhaul	36 hrs	Fri 1/7/22	Mon 1/10/22
M.E.1 - 8, Cylinder piston rod stuffing boxes; Overhaul	48 hrs	Sat 1/8/22	Tue 1/11/22
M.E.1 - 8, Cylinder piston cooling gland boxes; Overhaul (16)	24 hrs	Tue 1/11/22	Thu 1/13/22
M.E.1 - 8, Cylinder fuel injectors; Overhaul	24 hrs	Fri 1/7/22	Sat 1/8/22
M.E.1 - 8, Cylinder covers relief valves; Overhaul	8 hrs	Sat 1/8/22	Sun 1/9/22
M.E.1 - 8, Cylinder starting air valve; Overhaul	32 hrs	Sun 1/9/22	Tue 1/11/22
M.E.1 - 8, Cylinder jacket cooling water inlet butterfly valves(8); inspect and service	16 hrs	Tue 1/11/22	Thu 1/13/22
M.E.1 - 8, Cylinder jacket cooling water outlet valves; inspect and service	8 hrs	Thu 1/13/22	Thu 1/13/22
M.E.1 - 8, Cylinder piston cooling water sight glasses; Inspect and clean	24 hrs	Thu 1/13/22	Fri 1/14/22
M.E.1 - 8, Cylinder lantern door sight glass; Inspect and clean	24 hrs	Sat 1/15/22	Sun 1/16/22

M.E.1 - 8, Cylinder flame arresters; Overhaul	8 hrs	Thu 1/13/22	Fri 1/14/22
M.E.1 - 8, Cylinder cover studs. Inspect and service if necessary	8 hrs	Fri 1/14/22	Fri 1/14/22
REASSEMBLY OF PARTS INCLUDE PISTON, LINERS	16.5 days	Sun 1/9/22	Tue 1/25/22
Clean & tap threads before Installing new Cylinder Studs (33) Not needed)	1 min	Sun 1/9/22	Sun 1/9/22
Install new gasket and close 1-8 liners plug space doors	12 hrs	Tue 1/18/22	Wed 1/19/22
Install M.E 1-8 cylinders jacket rings	4 hrs	Fri 1/14/22	Fri 1/14/22
Install M.E. 1 - 8, Cylinders piston cooling gland boxes	8 hrs	Tue 1/11/22	Tue 1/11/22
Install M.E. Cylinders liners as per removal	16 hrs	Tue 1/18/22	Wed 1/19/22
Install M.E. 1 - 8 Cylinders lubricator quills	24 hrs	Wed 1/19/22	Fri 1/21/22
Prove lubrication	24 hrs	Wed 1/19/22	Fri 1/21/22
Install M.E. 1- 8, Cylinders piston rod stuffing boxes	8 hrs	Tue 1/18/22	Wed 1/19/22
Install 1 - 8 Pistons and measure clearances between piston skirt and liner	24 hrs	Fri 1/21/22	Sat 1/22/22
Tighten M.E. 1 - 8, Cylinder piston rod nuts	10 hrs	Fri 1/21/22	Fri 1/21/22
Install M.E. 1 - 8, Cylinders stand pipes	16 hrs	Sat 1/22/22	Sun 1/23/22
Install M.E. 1 - 8, Cylinders covers	8 hrs	Tue 1/25/22	Tue 1/25/22
Install L Accessories on M.E. 1 - 8, cylinder covers	8 hrs	Tue 1/25/22	Tue 1/25/22
M.E. MISCELLANEOUS MTCE. ACTIVITIES	11.75 days	Thu 1/13/22	Tue 1/25/22
Unit NO.2 tie-rod bolts; check, verify tightness and replace as necessary	30 hrs	Thu 1/13/22	Sat 1/15/22
Unit NO.2 M.E Lateral bolts; Check, Verify tightness and replace as necessary	32 hrs	Sat 1/15/22	Tue 1/18/22
Unit NO.2 M.E. foundation bolts; check and tighten	24 hrs	Tue 1/18/22	Thu 1/20/22
Modify the frwd and aft fuel inkage covers as to easy access to FQS	8 hrs	Thu 1/20/22	Thu 1/20/22
Side stays overhaul	4 hrs	Fri 1/21/22	Fri 1/21/22
Turning gear check	4 hrs	Fri 1/21/22	Fri 1/21/22
T/C air seal vent check/clean	4 hrs	Mon 1/24/22	Mon 1/24/22
Scavenging air water drain orifices check	6 hrs	Mon 1/24/22	Tue 1/25/22
No.2 M.E. ACCESS DOORS CLOSING	1.67 days	Thu 1/20/22	Sat 1/22/22
Renew gaskets & close economizer doors	4 hrs	Thu 1/20/22	Thu 1/20/22
Renew gaskets & close liners plug space doors	4 hrs	Thu 1/20/22	Fri 1/21/22
Renew gaskets & close M.E. Lantern doors	2 hrs	Fri 1/21/22	Fri 1/21/22
Renew gaskets & close M.E. Upper & lower scavenge space doors (upper complete)	4 hrs	Fri 1/21/22	Fri 1/21/22
Renew gaskets & close M.E. Crankcase side doors	2 hrs	Fri 1/21/22	Fri 1/21/22
Renew gaskets & close M.E. Pup doors	2 hrs	Fri 1/21/22	Fri 1/21/22
Renew gaskets & close manifold doors	1 hr	Sat 1/22/22	Sat 1/22/22

SCAVENGE AIR RECIEVER MAINTENANCE	8.41 days	Fri 1/7/22	Sat 1/15/22
Remove all reed valves (Scavenge door)	4 hrs	Fri 1/7/22	Fri 1/7/22
Remove all water separators	2 hrs	Fri 1/7/22	Fri 1/7/22
Remove, Clean, repair & reinstall scavenge air receiver drain lines (2) FWD. & AFT.	16 hrs	Fri 1/7/22	Sat 1/8/22
Remove, Clean & reinstall sight glasses (2) for pup space	2 hrs	Sat 1/8/22	Sat 1/8/22
Overhaul pup flap mechanism	8 hrs	Sat 1/8/22	Sun 1/9/22
Repair damaged areas and apply epoxy to these areas (as required)	24 hrs	Sun 1/9/22	Tue 1/11/22
Inspect & service reed valves (Scavenge air valves) (56)	32 hrs	Tue 1/11/22	Fri 1/14/22
Reinstall reed valves (scavenge air)	8 hrs	Fri 1/14/22	Fri 1/14/22
Reinstall water separators	8 hrs	Fri 1/14/22	Sat 1/15/22
Scavenging air water separators air gap check	2 hrs	Sat 1/15/22	Sat 1/15/22
M.E. STARTING AIR SYSTEM	2.38 days	Fri 1/7/22	Sun 1/9/22
AUTOMATIC SHUT OFF VALVE	0.38 days	Fri 1/7/22	Fri 1/7/22
Inspect & service automatic shut off valve	4 hrs	Fri 1/7/22	Fri 1/7/22
Starting air drain & test piping; inspect for blockage & clean (Starting air valve)	4 hrs	Fri 1/7/22	Fri 1/7/22
STARTING AIR DISTRIBUTOR & DISTRIBUTION VALVES (8)	1.38 days	Sat 1/8/22	Sun 1/9/22
Starting air distribution valves (8); Inspect & service	8 hrs	Sat 1/8/22	Sat 1/8/22
Starting air distributor; Inspect & service	8 hrs	Sun 1/9/22	Sun 1/9/22
MANIFOLD COMPENSATORS INSPECTION & MAINTENANCE - H. REID	3.42 days	Fri 1/7/22	Mon 1/10/22
Cooling down of exhaust manifold	24 hrs	Fri 1/7/22	Sun 1/9/22
Inspect M.E. 1 - 8 sections of exhaust manifolds for cracks	8 hrs	Sun 1/9/22	Sun 1/9/22
Inspect manifold doors (FWD. & AFT.)	2 hrs	Sun 1/9/22	Mon 1/10/22
Check foundation bolts	8 hrs	Mon 1/10/22	Mon 1/10/22
MAIN ENGINE AUXILIARY SYSTEMS	18.46 days	Fri 1/7/22	Tue 1/25/22
UNIT No 2 COOLERS & PIPES CLEANING (11 hrs.)	12.79 days	Fri 1/7/22	Wed 1/19/22
SCAVENGE AIR COOLERS	12.75 days	Fri 1/7/22	Wed 1/19/22
SCAVENGE AIR COOLER_FWD. (upper & lower)	6.38 days	Fri 1/7/22	Thu 1/13/22
Remove sea water pipes	2 hrs	Fri 1/7/22	Fri 1/7/22
Unbolt & remove coolers covers	2 hrs	Fri 1/7/22	Fri 1/7/22
Remove scavenge air coolers from cooler housing & plant	4 hrs	Fri 1/7/22	Fri 1/7/22
Soak coolers (cooler was change)	16 hrs	Fri 1/7/22	Fri 1/7/22
Clean cooler fins	12 hrs	Sat 1/8/22	Sun 1/9/22
Rod clean cooler tubes	24 hrs	Sun 1/9/22	Tue 1/11/22

Install new anodes to cooler covers	3 hrs	Tue 1/11/22	Tue 1/11/22
Pressure test cooler & check for leaks (local)	4 hrs	Tue 1/11/22	Tue 1/11/22
Inspect & clear vent / drain pipes	2 hrs	Tue 1/11/22	Tue 1/11/22
Reinstall cooler to housing	6 hrs	Tue 1/11/22	Wed 1/12/22
Replace gasket, O-ring & install cooler covers	4 hrs	Wed 1/12/22	Wed 1/12/22
Reinstall scavenge air coolers sea water pipes	4 hrs	Wed 1/12/22	Thu 1/13/22
SCAVENGE AIR COOLERS_AFT. (Peppe) (upper & lower)	6.38 days	Thu 1/13/22	Wed 1/19/22
Remove sea water pipes	2 hrs	Thu 1/13/22	Thu 1/13/22
Unbolt & remove cooler covers	2 hrs	Thu 1/13/22	Thu 1/13/22
Remove scavenge air coolers from cooler housing & plant	4 hrs	Thu 1/13/22	Thu 1/13/22
Soak coolers (Cooler was change)	18 hrs	Thu 1/13/22	Fri 1/14/22
Clean cooler fins	12 hrs	Fri 1/14/22	Sat 1/15/22
Rod clean cooler tubes (Sea water side)	24 hrs	Sat 1/15/22	Mon 1/17/22
Install new anodes to cooler covers	3 hrs	Mon 1/17/22	Mon 1/17/22
Pressure test cooler & check for leaks (local)	4 hrs	Mon 1/17/22	Tue 1/18/22
Inspect & clear vent / drain pipes	8 hrs	Mon 1/17/22	Tue 1/18/22
Reinstall cooler to housing	6 hrs	Tue 1/18/22	Wed 1/19/22
Replace gasket, O-ring & install new cooler covers	4 hrs	Wed 1/19/22	Wed 1/19/22
Reinstall scavenge air coolers sea water pipes	4 hrs	Wed 1/19/22	Wed 1/19/22
PISTON COOLER (SEA WATER SIDE)	1.04 days	Fri 1/7/22	Sat 1/8/22
Remove cooler covers	1 hr	Fri 1/7/22	Fri 1/7/22
Inspect & clear vent pipes	1 hr	Fri 1/7/22	Fri 1/7/22
Clean cooler sea water side	4 hrs	Fri 1/7/22	Fri 1/7/22
Inspect anodes & replace as necessary	4 hrs	Fri 1/7/22	Fri 1/7/22
Replace piston cooler gasket & reinstall cooler covers	2 hrs	Fri 1/7/22	Sat 1/8/22
JACKET COOLER (SEA WATER SIDE)	1.04 days	Sat 1/8/22	Sun 1/9/22
Remove cooler covers	1 hr	Sat 1/8/22	Sat 1/8/22
Inspect & clear vent pipes	1 hr	Sat 1/8/22	Sat 1/8/22
Clean cooler sea water side	4 hrs	Sat 1/8/22	Sat 1/8/22
Inspect anodes & replace as necessary	4 hrs	Sat 1/8/22	Sat 1/8/22
Replace jacket cooler gasket & reinstall cooler covers	2 hrs	Sun 1/9/22	Sun 1/9/22
LUBE OIL COOLER (SEA WATER SIDE)	1.04 days	Sun 1/9/22	Mon 1/10/22
Remove cooler covers	1 hr	Sun 1/9/22	Sun 1/9/22

Inspect & clear vent pipes	1 hr	Sun 1/9/22	Sun 1/9/22
Clean cooler sea water side	4 hrs	Sun 1/9/22	Sun 1/9/22
Inspect anodes & replace as necessary	4 hrs	Sun 1/9/22	Mon 1/10/22
Replace lube oil cooler gasket & reinstall cooler covers	2 hrs	Mon 1/10/22	Mon 1/10/22
PIPES CLEANING	1.92 days	Mon 1/10/22	Wed 1/12/22
M.e. 1 - 8, cylinder fuel injector cooling water inlet & outlet headers	4 hrs	Mon 1/10/22	Mon 1/10/22
Lantern space drain pipe to piston rod pack tank	8 hrs	Mon 1/10/22	Tue 1/11/22
Remove, clear M.e. jacket plug drain line & reinstall after	8 hrs	Tue 1/11/22	Wed 1/12/22
ECONOMIZER CLEANING	1.21 days	Tue 1/18/22	Wed 1/19/22
Water wash economizer (power wash) (valves to remove based on inspection)	16 hrs	Tue 1/18/22	Wed 1/19/22
UNIT NO.2 PUMPS MAINTENANCE	11.42 days	Fri 1/7/22	Tue 1/18/22
MAIN ENGINE No.2 AUX. VALVES OVERHAUL / INSPECTION & SERVICING	14.04 days	Fri 1/7/22	Fri 1/21/22
MISCELLANEOUS EQUIPMENT MAINTENANCE (VALVES ETC.)	18.17 days	Fri 1/7/22	Tue 1/25/22
SOOT BLOWER SYSTEM	1.17 days	Fri 1/7/22	Sat 1/8/22
2A SOOT BLOWER	0.29 days	Fri 1/7/22	Fri 1/7/22
Soot blower gear train ;Inspect and service	2 hrs	Fri 1/7/22	Fri 1/7/22
Puppet valve; Inspect and service	2 hrs	Fri 1/7/22	Fri 1/7/22
Inspect & Replace packing if necessary	2 hrs	Fri 1/7/22	Fri 1/7/22
2B SOOT BLOWER	0.88 days	Fri 1/7/22	Sat 1/8/22
Soot blower gear train; Inspect and service	2 hrs	Fri 1/7/22	Fri 1/7/22
Puppet Valve; Inspect and service	2 hrs	Sat 1/8/22	Sat 1/8/22
Inspect & replace packing if necessary	2 hrs	Sat 1/8/22	Sat 1/8/22
LUBE OIL FLUSH (Pipes to be properly labelled prior to removal)	18.17 days	Fri 1/7/22	Tue 1/25/22
Lube oil system piping; Inspect & clean as necessary	8 hrs	Fri 1/7/22	Fri 1/7/22
Reinstall piping	4 hrs	Fri 1/7/22	Sat 1/8/22
Install hoses, blind flanges & Collection bags for lube oil system flushing	8 hrs	Mon 1/24/22	Tue 1/25/22
Restore piping to normal after line oil flush	5 hrs	Fri 1/7/22	Fri 1/7/22
MMD CORRECTIVES	5.38 days	Fri 1/7/22	Wed 1/12/22
INTER DEPARTMENTAL. PROJECTS ACTIVITIES	2.46 days	Fri 1/7/22	Sun 1/9/22
SERVICES DEPT. ACTIVITIES	13.38 days	Fri 1/7/22	Thu 1/20/22
STATUTORY INSPECTION (Nigel)	2.17 days	Fri 1/21/22	Sun 1/23/22
WARTISILA MAIN ENGINE WORK ACTIVITIES	24.71 days	Fri 1/7/22	Mon 1/31/22

WARTSILA MAIN ENGINE BEARINGS INSPECTION / REPLACEMENT(Initial Crankshaft deflection, Pistons removal before Bearings works)	20.79 days	Fri 1/7/22	Thu 1/27/22
PERMT ACQUISITION & CANCELLATION	20.79 days	Fri 1/7/22	Thu 1/27/22
Start Main engine Overhaul	0 hrs	Fri 1/7/22	Fri 1/7/22
Acquire LOTO. For main engine bearings inspection / replacement (MMD / Wartsila)	1 hr	Fri 1/7/22	Fri 1/7/22
Cancel LOTO For main engine bearings inspection / replacement (MMD/ Wartsila)	1 hr	Thu 1/27/22	Thu 1/27/22
CRANKSHAFT DEFLECTION	20.42 days	Fri 1/7/22	Thu 1/27/22
Measure Crankshaft deflection & Bearing clearances - Initial	4 hrs	Fri 1/7/22	Fri 1/7/22
Measure Crankshaft deflection & Bearing clearances - Final (to be done after all pistons are installed)	4 hrs	Thu 1/27/22	Thu 1/27/22
WATER SEPARATOR MODIFICATION	3 days	Sat 1/15/22	Tue 1/18/22
Install blind into water separator housing as is necessary	72 hrs	Sat 1/15/22	Tue 1/18/22
Complete water separator modification	0 hrs	Tue 1/18/22	Tue 1/18/22
MAIN ENGINE BEARINGS OVERHAUL	20.25 days	Fri 1/7/22	Thu 1/27/22
ENGINE MAIN BEARING INSPECTION / REPLACEMENT	19.29 days	Sat 1/8/22	Thu 1/27/22
ENGINE MAIN BEARING #2 INSPECTION / REPLACEMENT	1.21 days	Sat 1/8/22	Sun 1/9/22
Remove Lines from Main Bearing	1 hr	Sat 1/8/22	Sat 1/8/22
Loosen & remove Thrust Bolts	2 hrs	Sat 1/8/22	Sat 1/8/22
Remove Cap from Main Bearing	1 hr	Sat 1/8/22	Sat 1/8/22
Remove Main Bearing	2 hrs	Sat 1/8/22	Sat 1/8/22
Inspect Main Bearing / Journal & polish as necessary	4 hrs	Sat 1/8/22	Sat 1/8/22
Install Main Bearing	2 hrs	Sat 1/8/22	Sun 1/9/22
Install Cap to Main Bearing	2 hrs	Sun 1/9/22	Sun 1/9/22
Install Lube Oil Lines to Main Bearing	2 hrs	Sun 1/9/22	Sun 1/9/22
ENGINE MAIN BEARING #5 INSPECTION / REPLACEMENT	1.71 days	Mon 1/17/22	Wed 1/19/22
Remove Lines from Main Bearing	1 hr	Mon 1/17/22	Mon 1/17/22
Loosen & remove Thrust Bolts	2 hrs	Mon 1/17/22	Mon 1/17/22
Remove Cap from Main Bearing	1 hr	Mon 1/17/22	Mon 1/17/22
Remove Main Bearing	2 hrs	Mon 1/17/22	Tue 1/18/22
Inspect Main Bearing / Journal & polish as necessary	4 hrs	Tue 1/18/22	Tue 1/18/22
Install Main Bearing	2 hrs	Tue 1/18/22	Tue 1/18/22
Install Cap to Main Bearing	2 hrs	Tue 1/18/22	Tue 1/18/22
Install Lube Oil Lines to Main Bearing	2 hrs	Tue 1/18/22	Wed 1/19/22
ENGINE MAIN BEARING #7 INSPECTION / REPLACEMENT	1.25 days	Wed 1/19/22	Thu 1/20/22

Remove Lines from Main Bearing	1 hr	Wed 1/19/22	Wed 1/19/22
Loosen & remove Thrust Bolts	2 hrs	Wed 1/19/22	Wed 1/19/22
Remove Cap from Main Bearing	1 hr	Wed 1/19/22	Wed 1/19/22
Remove Main Bearing	2 hrs	Wed 1/19/22	Wed 1/19/22
Inspect Main Bearing / Journal & polish as necessary	4 hrs	Wed 1/19/22	Wed 1/19/22
Install Main Bearing	2 hrs	Wed 1/19/22	Thu 1/20/22
Install Cap to Main Bearing	2 hrs	Thu 1/20/22	Thu 1/20/22
Install Lube Oil Lines to Main Bearing	2 hrs	Thu 1/20/22	Thu 1/20/22
ENGINE MAIN BEARING #1 INSPECTION / REPLACEMENT	1.71 days	Mon 1/24/22	Wed 1/26/22
Remove Lines from Main Bearing	1 hr	Mon 1/24/22	Mon 1/24/22
Loosen & remove Thrust Bolts	2 hrs	Mon 1/24/22	Mon 1/24/22
Remove Cap from Main Bearing	1 hr	Mon 1/24/22	Mon 1/24/22
Remove Main Bearing	2 hrs	Tue 1/25/22	Tue 1/25/22
Inspect Main Bearing / Journal & polish as necessary	4 hrs	Tue 1/25/22	Tue 1/25/22
Install Main Bearing	2 hrs	Tue 1/25/22	Tue 1/25/22
Install Cap to Main Bearing	2 hrs	Tue 1/25/22	Tue 1/25/22
Install Lube Oil Lines to Main Bearing	2 hrs	Tue 1/25/22	Wed 1/26/22
ENGINE MAIN BEARING #6 INSPECTION / REPLACEMENT (If time allows)	1.25 days	Wed 1/26/22	Thu 1/27/22
Remove Lines from Main Bearing	1 hr	Wed 1/26/22	Wed 1/26/22
Loosen & remove Thrust Bolts	2 hrs	Wed 1/26/22	Wed 1/26/22
Remove Cap from Main Bearing	1 hr	Wed 1/26/22	Wed 1/26/22
Remove Main Bearing	2 hrs	Wed 1/26/22	Wed 1/26/22
Inspect Main Bearing / Journal & polish as necessary	4 hrs	Wed 1/26/22	Wed 1/26/22
Install Main Bearing	2 hrs	Thu 1/27/22	Thu 1/27/22
Install Cap to Main Bearing	2 hrs	Thu 1/27/22	Thu 1/27/22
Install Lube Oil Lines to Main Bearing	2 hrs	Thu 1/27/22	Thu 1/27/22
CROSSHEAD BEARING & PIN INSPECTION / REPLACEMENT	15.08 days	Sun 1/9/22	Mon 1/24/22
CROSSHEAD BEARING & PIN #1 INSPECTION / BEARING REPLACEMENT	1.77 days	Sun 1/9/22	Tue 1/11/22
Loosen (1) bearing trust bolts	2 hrs	Sun 1/9/22	Sun 1/9/22
Remove Cap from Crosshead Bearing	2 hrs	Sun 1/9/22	Sun 1/9/22
Lift Crosshead Pin out of saddle	2 hrs	Sun 1/9/22	Sun 1/9/22
Remove Lower Half Crosshead Bearing Shell	0.5 hrs	Mon 1/10/22	Mon 1/10/22
Inspect Crosshead Pin & polish if necessary	3 hrs	Mon 1/10/22	Mon 1/10/22

Inspect Saddle	1 hr	Mon 1/10/22	Mon 1/10/22
Inspect Guide Shoe	1 hr	Mon 1/10/22	Mon 1/10/22
Install Lower Half Bearing Shell	0.5 hrs	Mon 1/10/22	Mon 1/10/22
Install Crosshead Pin	2.5 hrs	Mon 1/10/22	Mon 1/10/22
Install Cap to Crosshead Bearing	2 hrs	Mon 1/10/22	Mon 1/10/22
Tighten (1) bearing trust bolts	1 hr	Mon 1/10/22	Tue 1/11/22
CROSSHEAD BEARING & PIN # 8 INSPECTION / REPLACEMENT	2.06 days	Tue 1/11/22	Thu 1/13/22
Loosen (8) bearing trust bolts	2 hrs	Tue 1/11/22	Tue 1/11/22
Remove Cap from Crosshead Bearing	2 hrs	Tue 1/11/22	Tue 1/11/22
Lift Crosshead Pin out of saddle	2 hrs	Tue 1/11/22	Tue 1/11/22
Remove Lower Half Crosshead Bearing Shell	0.5 hrs	Tue 1/11/22	Tue 1/11/22
Inspect Crosshead Pin & polish if necessary	3 hrs	Tue 1/11/22	Wed 1/12/22
Inspect Saddle	1 hr	Wed 1/12/22	Wed 1/12/22
Inspect Guide Shoe	1 hr	Wed 1/12/22	Wed 1/12/22
Install Lower Half Bearing Shell	0.5 hrs	Wed 1/12/22	Wed 1/12/22
Install Crosshead Pin	2.5 hrs	Wed 1/12/22	Wed 1/12/22
Install Cap to Crosshead Bearing	2 hrs	Wed 1/12/22	Thu 1/13/22
Tighten (8) bearing trust bolts	1 hr	Thu 1/13/22	Thu 1/13/22
CROSSHEAD BEARING & PIN # 7 INSPECTION / REPLACEMENT	4.06 days	Thu 1/20/22	Mon 1/24/22
Loosen (7) bearing trust bolts	2 hrs	Thu 1/20/22	Thu 1/20/22
Remove Cap from Crosshead Bearing	2 hrs	Thu 1/20/22	Fri 1/21/22
Lift Crosshead Pin out of saddle	2 hrs	Fri 1/21/22	Fri 1/21/22
Remove Lower Half Crosshead Bearing Shell	0.5 hrs	Fri 1/21/22	Fri 1/21/22
Inspect Crosshead Pin & polish if necessary (Was replaced)	3 hrs	Fri 1/21/22	Fri 1/21/22
Inspect Saddle	1 hr	Fri 1/21/22	Fri 1/21/22
Inspect Guide Shoe	1 hr	Fri 1/21/22	Fri 1/21/22
Install Lower Half Bearing Shell	0.5 hrs	Mon 1/24/22	Mon 1/24/22
Install Crosshead Pin	2.5 hrs	Mon 1/24/22	Mon 1/24/22
Install Cap to Crosshead Bearing	2 hrs	Mon 1/24/22	Mon 1/24/22
Tighten (7) bearing trust bolts	1 hr	Mon 1/24/22	Mon 1/24/22
CROSSHEAD BEARING & PIN # 5 INSPECTION / REPLACEMENT	1.31 days	Tue 1/11/22	Wed 1/12/22
Loosen (5) bearing trust bolts	2 hrs	Tue 1/11/22	Tue 1/11/22

Remove Cap from Crosshead Bearing	2 hrs	Tue 1/11/22	Tue 1/11/22
Lift Crosshead Pin out of saddle	2 hrs	Tue 1/11/22	Tue 1/11/22
Remove Lower Half Crosshead Bearing Shell	0.5 hrs	Tue 1/11/22	Tue 1/11/22
Inspect Crosshead Pin & polish if necessary	3 hrs	Tue 1/11/22	Tue 1/11/22
Inspect Saddle	1 hr	Tue 1/11/22	Wed 1/12/22
Inspect Guide Shoe	1 hr	Wed 1/12/22	Wed 1/12/22
Install Lower Half Bearing Shell	0.5 hrs	Wed 1/12/22	Wed 1/12/22
Install Crosshead Pin	2.5 hrs	Wed 1/12/22	Wed 1/12/22
Install Cap to Crosshead Bearing	2 hrs	Wed 1/12/22	Wed 1/12/22
Tighten (5) bearing trust bolts	1 hr	Wed 1/12/22	Wed 1/12/22
CROSSHEAD BEARING & PIN # 6 INSPECTION / REPLACEMENT	1.77 days	Wed 1/12/22	Fri 1/14/22
Loosen (6) bearing trust bolts	2 hrs	Wed 1/12/22	Wed 1/12/22
Remove Cap from Crosshead Bearing	2 hrs	Wed 1/12/22	Thu 1/13/22
Lift Crosshead Pin out of saddle	2 hrs	Thu 1/13/22	Thu 1/13/22
Inspect Crosshead Pin & polish if necessary	0.5 hrs	Thu 1/13/22	Thu 1/13/22
Remove Lower Half Crosshead Bearing Shell	3 hrs	Thu 1/13/22	Thu 1/13/22
Inspect Saddle	1 hr	Thu 1/13/22	Thu 1/13/22
Inspect Guide Shoe	1 hr	Thu 1/13/22	Thu 1/13/22
Install Lower Half Bearing Shell	0.5 hrs	Thu 1/13/22	Thu 1/13/22
Install Crosshead Pin	2.5 hrs	Thu 1/13/22	Thu 1/13/22
Install Cap to Crosshead Bearing	2 hrs	Thu 1/13/22	Fri 1/14/22
Tighten (6) bearing trust bolts	1 hr	Fri 1/14/22	Fri 1/14/22
BOTTOM END (BIG END) BEARING INSPECTION	16.04 days	Fri 1/7/22	Sun 1/23/22
BOTTOM END (BIG END) BEARING # 1 INSPECTION / REPLACEMENT	1.25 days	Thu 1/13/22	Fri 1/14/22
Remove crankpin bearing cap	3 hrs	Thu 1/13/22	Thu 1/13/22
Remove crankpin bearing	2 hrs	Thu 1/13/22	Thu 1/13/22
Inspect crankpin bearing	1 hr	Thu 1/13/22	Thu 1/13/22
Inspect crankpin	1 hr	Thu 1/13/22	Thu 1/13/22
Polish crankpin	4 hrs	Thu 1/13/22	Fri 1/14/22
Install crankpin bearing	3 hrs	Fri 1/14/22	Fri 1/14/22
Install crankpin bearing cap	2 hrs	Fri 1/14/22	Fri 1/14/22
BOTTOM END (BIG END) BEARING # 3 INSPECTION / REPLACEMENT	1.71 days	Fri 1/14/22	Sun 1/16/22
Remove crankpin bearing cap	3 hrs	Fri 1/14/22	Fri 1/14/22

Remove crankpin bearing	2 hrs	Fri 1/14/22	Sat 1/15/22
Inspect crankpin bearing	1 hr	Sat 1/15/22	Sat 1/15/22
Inspect crankpin	1 hr	Sat 1/15/22	Sat 1/15/22
Polish crankpin	4 hrs	Sat 1/15/22	Sat 1/15/22
Install crankpin bearing	3 hrs	Sat 1/15/22	Sat 1/15/22
Install crankpin bearing cap	2 hrs	Sat 1/15/22	Sun 1/16/22
BOTTOM END (BIG END) BEARING # 4 INSPECTION / REPLACEMENT	1.25 days	Sun 1/16/22	Mon 1/17/22
Remove crankpin bearing cap	3 hrs	Sun 1/16/22	Sun 1/16/22
Remove crankpin bearing	2 hrs	Sun 1/16/22	Sun 1/16/22
Inspect crankpin bearing	1 hr	Sun 1/16/22	Sun 1/16/22
Inspect crankpin	1 hr	Sun 1/16/22	Sun 1/16/22
Polish crankpin	4 hrs	Sun 1/16/22	Mon 1/17/22
Install crankpin bearing	3 hrs	Mon 1/17/22	Mon 1/17/22
Install crankpin bearing cap	2 hrs	Mon 1/17/22	Mon 1/17/22
BOTTOM END (BIG END) BEARING #8 INSPECTION / REPLACEMENT	0 days	Thu 1/13/22	Thu 1/13/22
CAMSHAFT INSPECTION / SERVICING (Visual inspection of #1,2,3 4,5,6,7,8)	16.04 days	Fri 1/7/22	Sun 1/23/22
Cam carriers & fuel cam inspection	4 hrs	Wed 1/19/22	Wed 1/19/22
Measured camshaft bearing clearances	4 hrs	Wed 1/19/22	Wed 1/19/22
Inspection of camshaft bearings	4 hrs	Wed 1/19/22	Thu 1/20/22
Tightening of fuel cams	4 hrs	Thu 1/20/22	Thu 1/20/22
Measured camshaft bearing clearances (final)	4 hrs	Thu 1/20/22	Thu 1/20/22
FUEL PUMP BLOCK (4) & LINKAGE INSPECTION / OVERHAUL	16.04 days	Fri 1/7/22	Sun 1/23/22
PUMP BLOCK #1	14.35 days	Fri 1/7/22	Fri 1/21/22
Dismantle & remove the tension covers	2 hrs	Fri 1/7/22	Fri 1/7/22
Remove the fuel pump block	4 hrs	Fri 1/7/22	Sat 1/8/22
Dismantle of fuel pump block components	6 hrs	Sat 1/8/22	Sat 1/8/22
Clean the fuel pump block components	2 hrs	Sat 1/8/22	Sat 1/8/22
Inspect service components (valves, push rod and plungers)	6 hrs	Sat 1/8/22	Sun 1/9/22
Reassemble pump block components	2 hrs	Sun 1/9/22	Sun 1/9/22
Inspect&service fuel pump block isolation valve	2 hrs	Sun 1/9/22	Sun 1/9/22
Inspect&service fuel pump block safety cut out	6 hrs	Sun 1/9/22	Mon 1/10/22
Dismantle fuel pump intermediate piece	2 hrs	Mon 1/10/22	Mon 1/10/22
Clean up the space	2 hrs	Mon 1/10/22	Mon 1/10/22

Dismantle& inspection& service of fuel pump driving piston	2 hrs	Mon 1/10/22	Mon 1/10/22
Dismantle& inspection& service of fuel pump driving piston guide bush	4 hrs	Mon 1/10/22	Tue 1/11/22
Reinstall the guide bush	4 hrs	Tue 1/11/22	Tue 1/11/22
Reinstal the driving pistons	4 hrs	Tue 1/11/22	Tue 1/11/22
Reinstal the fuel pump components	2 hrs	Fri 1/21/22	Fri 1/21/22
PUMP BLOCK #2	14.35 days	Fri 1/7/22	Fri 1/21/22
Dismantle & remove the tension covers	2 hrs	Fri 1/7/22	Fri 1/7/22
Remove the fuel pump block	4 hrs	Sat 1/8/22	Sat 1/8/22
Dismantle of fuel pump block components	6 hrs	Sat 1/8/22	Sun 1/9/22
Clean the fuel pump block components	2 hrs	Sat 1/8/22	Sun 1/9/22
Inspect service components (valves, push rod and plungers)	6 hrs	Sun 1/9/22	Sun 1/9/22
Reasamble pump block components	6 hrs	Sun 1/9/22	Mon 1/10/22
Inspect&service fuel pump block isolation valve	1 hr	Sun 1/9/22	Sun 1/9/22
Inspect&service fuel pump block safety cut out	6 hrs	Mon 1/10/22	Mon 1/10/22
Dismantle fuel pump intermediate piece	2 hrs	Mon 1/10/22	Tue 1/11/22
Clean up the space	1 hr	Tue 1/11/22	Tue 1/11/22
Dismantle& inspection& service of fuel pump driving piston	2 hrs	Tue 1/11/22	Tue 1/11/22
Dismantle& inspection& service of fuel pump driving piston guide bush	2 hrs	Tue 1/11/22	Tue 1/11/22
Reinstall the guide bush	6 hrs	Tue 1/11/22	Wed 1/12/22
Reinstal the driving pistons	6 hrs	Wed 1/12/22	Wed 1/12/22
Reinstal the fuel pump components	2 hrs	Fri 1/21/22	Fri 1/21/22
PUMP BLOCK #3	14.94 days	Fri 1/7/22	Sat 1/22/22
Dismantle & remove the tension covers	2 hrs	Fri 1/7/22	Fri 1/7/22
Remove the fuel pump block	4 hrs	Sat 1/8/22	Sat 1/8/22
Dismantle of fuel pump block components	6 hrs	Sun 1/9/22	Sun 1/9/22
Clean the fuel pump block components	2 hrs	Sun 1/9/22	Sun 1/9/22
Inspect service components (valves, push rod and plungers)	6 hrs	Mon 1/10/22	Mon 1/10/22
Reasamble pump block components	6 hrs	Mon 1/10/22	Mon 1/10/22
Inspect&service fuel pump block isolation valve	1 hr	Sun 1/9/22	Sun 1/9/22
Inspect&service fuel pump block safety cut out	6 hrs	Mon 1/10/22	Tue 1/11/22
Dismantle fuel pump intermediate piece	1 hr	Tue 1/11/22	Tue 1/11/22
Clean up the space	1 hr	Tue 1/11/22	Tue 1/11/22
Dismantle& inspection& service of fuel pump driving piston	2 hrs	Tue 1/11/22	Tue 1/11/22

Dismantle& inspection& service of fuel pump driving piston guide bush	2 hrs	Tue 1/11/22	Tue 1/11/22
Reinstall the guide bush	6 hrs	Wed 1/12/22	Wed 1/12/22
Reinstal the driving pistons	6 hrs	Wed 1/12/22	Thu 1/13/22
Reinstal the fuel pump components	2 hrs	Fri 1/21/22	Sat 1/22/22
PUMP BLOCK #4	15.75 days	Fri 1/7/22	Sun 1/23/22
Dismantle & remove the tension covers	2 hrs	Fri 1/7/22	Fri 1/7/22
Remove the fuel pump block	4 hrs	Sat 1/8/22	Sun 1/9/22
Dismantle of fuel pump block components	6 hrs	Sun 1/9/22	Sun 1/9/22
Clean the fuel pump block components	4 hrs	Sun 1/9/22	Sun 1/9/22
Inspect service components (valves, push rod and plungers)	6 hrs	Mon 1/10/22	Tue 1/11/22
Reasamble pump block components	6 hrs	Tue 1/11/22	Tue 1/11/22
Inspect&service fuel pump block isolation valve	1 hr	Mon 1/10/22	Mon 1/10/22
Inspect&service fuel pump block safety cut out	6 hrs	Tue 1/11/22	Tue 1/11/22
Dismantle fuel pump intermediate piece	1 hr	Tue 1/11/22	Tue 1/11/22
Clean up the space	1 hr	Tue 1/11/22	Tue 1/11/22
Dismantle& inspection& service of fuel pump driving piston	2 hrs	Tue 1/11/22	Tue 1/11/22
Dismantle& inspection& service of fuel pump driving piston guide bush	2 hrs	Tue 1/11/22	Tue 1/11/22
Reinstall the guide bush	6 hrs	Wed 1/12/22	Thu 1/13/22
Reinstal the driving pistons	6 hrs	Thu 1/13/22	Thu 1/13/22
Reinstal the fuel pump components	2 hrs	Sat 1/22/22	Sun 1/23/22
FUEL PUMP REGULATING LINKAGE	9.31 days	Wed 1/12/22	Fri 1/21/22
Remove fuel regulating linkage	1 hr	Wed 1/12/22	Wed 1/12/22
Fuel linkage mechanism; Inspect and service	2 hrs	Wed 1/12/22	Wed 1/12/22
Re-Install fuel regulating linkage	2 hrs	Wed 1/12/22	Wed 1/12/22
Fuel pump timing	8 hrs	Thu 1/20/22	Fri 1/21/22
GRINDING ACTIVITIES (32 surfaces); 2 persons required for check valves replacement	14.13 days	Thu 1/13/22	Thu 1/27/22
Grinding of Cylinder Block landing surfaces (All 8 surfaces)	32 hrs	Thu 1/13/22	Sun 1/16/22
Grinding of Liners landing surfaces & replace check valves (lower) (All 8 surfaces)	1 min	Sun 1/16/22	Sun 1/16/22
Grinding of Liners landing surfaces (upper) (All 8 surfaces) (2,3,7&8)	20 hrs	Sun 1/16/22	Tue 1/18/22
Grinding of cylinders Covers landing surfaces (All 8 surfaces)	72 hrs	Tue 1/18/22	Tue 1/25/22
End Main engine Overhaul	0 hrs	Thu 1/27/22	Thu 1/27/22
INSTALLATION OF WATER SEPARATOR GAP SEAL	1.38 days	Mon 1/17/22	Tue 1/18/22
Install gap seal into water separator	16 hrs	Mon 1/17/22	Tue 1/18/22

ICM INSTALATION	18.38 days	Fri 1/7/22	Tue 1/25/22
Instalation of pressure transducers	8 hrs	Tue 1/25/22	Tue 1/25/22
Instalation of angle transducer	8 hrs	Fri 1/7/22	Fri 1/7/22
Instalation of pressure transducers plugs	8 hrs	Mon 1/10/22	Mon 1/10/22
Instalation of connection box	8 hrs	Tue 1/11/22	Tue 1/11/22
Puling the cable	8 hrs	Wed 1/12/22	Wed 1/12/22
Comisioning ICM	8 hrs	Thu 1/13/22	Thu 1/13/22
OIL MIST DEFLECTOR WORKS	1.38 days	Tue 1/11/22	Wed 1/12/22
Check/clean up all sensors	4 hrs	Tue 1/11/22	Tue 1/11/22
Remove all sensor and store them in a safe place	4 hrs	Tue 1/11/22	Tue 1/11/22
Install all sensors after overhaul	4 hrs	Wed 1/12/22	Wed 1/12/22
Test the system in service	4 hrs	Wed 1/12/22	Wed 1/12/22
METAL STICHING	2.9 days	Wed 1/12/22	Sat 1/15/22
Repair crack identified in Main Engine Cylinder Blocks Exhaust Pipe (as required)	16 hrs	Wed 1/12/22	Fri 1/14/22
Metal stitching of damaged areas of Exhaust manifolds (as required)	16 hrs	Fri 1/14/22	Sat 1/15/22
WARTSILA MISCELANEOUS MAIN ENGINE OVERHAUL SUPPORT / QUALITY ASSURANCE	24.71 days	Fri 1/7/22	Mon 1/31/22
Calibrate # 1 to 8 liners (prepare for further use liners in normal limits,)	8 hrs	Thu 1/13/22	Fri 1/14/22
Inspection of engine cylinder block & exhaust ports for cracks	16 hrs	Thu 1/13/22	Sat 1/15/22
Inspection & verification of main engine tie rod bolts tightness	16 hrs	Sun 1/16/22	Mon 1/17/22
Inspection & verification of main engine foundation bolts	12 hrs	Mon 1/17/22	Tue 1/18/22
Inspection, measurements & necessary polishing of liners	24 hrs	Tue 1/11/22	Thu 1/13/22
Inspection & verification of main engine lateral bolts tightness	24 hrs	Fri 1/14/22	Sun 1/16/22
Inspection & measurements of pistons crowns, skirts and rings	42 hrs	Thu 1/27/22	Mon 1/31/22
Support main engine lube oil system flushing & piping	5 hrs	Mon 1/31/22	Mon 1/31/22
Inspection/calibration of stand pipes and stuffing boxes	36 hrs	Fri 1/7/22	Sat 1/8/22
Inspection/calibration of piston rod stuffing boxes	8 hrs	Thu 1/13/22	Fri 1/14/22
Inspection/calibration of piston rods	16 hrs	Fri 1/14/22	Tue 1/18/22
Monitor engine bearings condition at engine run-in	24 hrs	Tue 1/18/22	Fri 1/21/22
Cylinder block water plugs; stop leakage	16 hrs	Fri 1/21/22	Tue 1/25/22
Final inspection of engine spaces & verification of components	16 hrs	Tue 1/25/22	Thu 1/27/22
Oil Mist Control Unit	0.33 days	Thu 1/27/22	Thu 1/27/22
Oil Mist deflector (1 to 9) ;Inspect and service.	8 hrs	Thu 1/27/22	Thu 1/27/22
MAIN ENGINE CYLINDER OIL LUBRICATING SYSTEM MAINTENANCE	2.25 days	Fri 1/7/22	Sun 1/9/22

Main engine cylinder oil lubricating pump (FWD); Inspect and service	0.58 days	Fri 1/7/22	Sat 1/8/22
Sight glasses/flow indicators (FWD); Inspect and clean	4 hrs	Fri 1/7/22	Fri 1/7/22
Lubrication lines(FWD); Check and clear lines	4 hrs	Fri 1/7/22	Fri 1/7/22
Inlet strainer (FWD); clean	6 hrs	Fri 1/7/22	Sat 1/8/22
Main engine cylinder oil Lubricating pump (AFT); Inspect and service	0.71 days	Sat 1/8/22	Sun 1/9/22
Sight glasses/ flow indicators (AFT); Inspect and clean	4 hrs	Sat 1/8/22	Sat 1/8/22
Lubrication lines(AFT); Check and clear lines	4 hrs	Sat 1/8/22	Sat 1/8/22
Inlet strainer(AFT); clean	6 hrs	Sat 1/8/22	Sun 1/9/22
Check the lubrication quills	4 hrs	Sun 1/9/22	Sun 1/9/22
RF #2 THRUST BEARINGS INSPECTION	4.38 days	Fri 1/7/22	Tue 1/11/22
Thrust bearing inspection/ Angle transducer instalation	4.38 days	Fri 1/7/22	Tue 1/11/22
Remove flywheel cover	2 hrs	Fri 1/7/22	Fri 1/7/22
Clean flywheel for inspection	4 hrs	Fri 1/7/22	Fri 1/7/22
Carry out inspection of flywheel	4 hrs	Fri 1/7/22	Mon 1/10/22
Inspect thrust bearing pads forward	4 hrs	Mon 1/10/22	Mon 1/10/22
Inspect thrust bearing pads aft	4 hrs	Mon 1/10/22	Tue 1/11/22
Install angle transducer	2 hrs	Tue 1/11/22	Tue 1/11/22
Install Lube Oil Lines to Main Bearing	2 hrs	Tue 1/11/22	Tue 1/11/22
Re-install cover to flywheel	2 hrs	Tue 1/11/22	Tue 1/11/22
End of RF #2 Major Overhaul 2022	0 hrs	Mon 1/31/22	Mon 1/31/22